

GROVE CITY, OHIO COUNCIL LEGISLATIVE AGENDA

December 19, 2022

6:30 Caucus

7:00 p.m. Regular Meeting

Call to Order: President Berry

Roll Call: Clerk of Council

Approval of Minutes

Welcome & Reading of Agenda: Pres. Berry

LANDS: Mr. Schottke

- Ordinance C-63-22 Approve the Rezoning of 144.27+ acres located North of State Route 665 and East of State Route 104 from SF-1 to PUD-R with Zoning Text. Second reading and public hearing. **Postponement requested.**
- Resolution CR-49-22 Approve the Development Plan for Beulah Park, Subarea C, permitting Lennar Homes Venture Collections. **Postponement requested.**
- Resolution CR-56-22 Approve the Development Plan for Communities at Plum Run located North of S.R. 665 and East of S.R. 104. **Postponement requested.**
- Resolution CR-68-22 Approve the Preliminary Development Plan for the Harris Property located North of S.R. 665 and West of Borror Road.
-

FINANCE: Mr. Holt

- Ordinance C-74-22 Appropriate \$1,900,000.00 from the Deposit Trust Fund and Reduce Appropriation Amounts for Various Funds. Second reading and public hearing.
- Ordinance C-75-22 Make Appropriations for Current Expenses and Other Expenditures for which the City of Grove City must provide during the twelve months ending December 31, 2023. Reading and public hearing.
-

Call for New Business

Call for Dept. Reports & Closing Comments

Adjourn

ON FILE: Minutes of: 12/05 & 08 Council; 12/06 Planning Commission

Date: 09/12/22
Introduced By: Mr. Schottke
Committee: Lands
Originated By: Plan. Comm.
Approved: _____
Emergency: 30 Days
Current Expense: _____

No.: C-63-22
1st Reading: 09/19/22
Public Notice: 09/20/22
2nd Reading: 11/07/22
Passed: _____ Rejected: _____
Codified: _____ Code No: _____
Passage Publication: _____

Postponed
to 12/5
12/19

ORDINANCE C-63-22

AN ORDINANCE FOR THE REZONING OF 144.27+ ACRES LOCATED NORTH OF STATE ROUTE 665 AND EAST OF STATE ROUTE 104 FROM SF-1 TO PUD-R WITH ZONING TEXT

WHEREAS, a petition was filed with the Planning Commission of the City of Grove City praying for the recommendation of said Commission in regard to the rezoning of certain premises hereinafter described; and

WHEREAS, the Planning Commission approved the rezoning on Sept. 06, 2022; and

WHEREAS, a copy of the ordinance, together with a map and plat and the report of the Planning Commission has been on file in the Clerk's office for thirty days for public inspection.

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF GROVE CITY, STATE OF OHIO, THAT:

SECTION 1. The following described premises are rezoned from SF-1 to PUD-R with zoning text:

Situated in the State of Ohio, County of Franklin, City of Grove City and being a part of Virginia Military Survey 1105 and being all of that tract of land as conveyed to S & W Huggett Ohio LLC, as recorded in Official Records, Instrument No. 200809300146421, Recorder's Office, Franklin County, Ohio, and being more fully described in Exhibit "A" attached hereto and made a part hereof.

SECTION 2. The comprehensive zoning map is hereby amended to conform to the provisions of this ordinance.

SECTION 3. This Ordinance shall take effect at the earliest opportunity allowed by law.

Ted. A. Berry, President of Council

Passed:
Effective:

Richard L. Stage, Mayor

Attest:

Tami K. Kelly, MMC, Clerk of Council

I Certify that this ordinance
is correct as to form.

Stephen J. Smith, Director of Law

Zoning Description

144.27 Acres

Situated in the State of Ohio, County of Franklin, City of Grove City, Virginia Military Survey No. 1105 and being all of that tract of land as conveyed to S & W Huggett Ohio LLC of record in Instrument Number 200809300146421, all deed references refer to the records of the Recorder's Office Franklin County, Ohio and described as follows:

Beginning at the northeasterly corner of said S & W Huggett Ohio LLC tract at the intersection of the southerly line extended of that plat entitled Scioto Meadows Section 1 Part 1 of record in Plat Book 89, Page 3, with the centerline of State Route 665;

Thence South 5°34'09" East with said centerline a distance of 2567.35 feet to an angle point in said centerline;

Thence North 82°15'14" West continuing with said centerline a distance of 2215.35 feet to the southeasterly corner of a 2.204 acre tract as conveyed to Steve M. and Sharon Doersam of record in Instrument Number 201101070004133;

Thence with the perimeter of said 2.204 acre tract the following courses:

North 7°25'40" East a distance of 481.11 feet to a corner thereof;

North 82°34'20" West a distance of 200.00 feet to a corner thereof;

South 7°25'39" West a distance of 480.00 feet to a corner thereof in the centerline of said State Route 665;

Thence North 82°15'14" West with said centerline a distance of 1629.33 feet to the southeasterly corner of a 1.520 acre tract as conveyed to Kip A. and Barbara R. Thompson of record in Instrument Number 200506210120647;

Thence with the perimeter of said 1.520 tract the following courses:

North 7°46'04" East a distance of 290.74 feet to a corner thereof;

North 80°15'21" West a distance of 180.18 feet to a point in the easterly right-of-way line of State Route 104;

Thence North 3°41'08" East with said easterly right-of-way line a distance of 543.33 feet to an angle point in said right-of-way line;

Thence North 86°26'33" West with said easterly right-of-way line a distance of 54.70 feet to a point in the centerline of said State Route 104;

Thence North 3°41'45" East with said centerline a distance of 113.01 feet to a point;

Zoning Description

144.27 Acres

Thence partly with the southerly line of a 1.0614 acre tract as conveyed to Daniel Riffe of record in Instrument Number 200309110290430 and partly with the southerly line of Scioto Meadows Section 1 Part 2 (Plat Book 89, Page 3) the following courses:

North 84°47'39" East a distance of 2928.35 feet to a corner thereof;

North 3°52'11" East a distance of 686.51 feet to a corner thereof;

North 85°01'11" East a distance of 950.27 feet to the **Point of Beginning** and containing **144.27 acres** of land more or less.


Subject to all covenants, restrictions, reservations, and easements contained in any instrument of record pertaining to the above described tract of land.

This description was prepared for Zoning Purposes only.

The Basis of Bearing for this description is South 05°34'09" East for a portion of State Route 665.



CESO, Inc.

 9.1-21

Jeffrey A. Miller, PS
Registered Surveyor No. 7211

Date 09/01/2021






POLITE HOMES OF OHIO, LLC
COMMUNITIES AT PLUM RUN
(HUGGETT PROPERTY)

BOUNDARY
EXHIBIT

JOB NO.	7833M
DESIGN	EAC
DRAWN	APC
CHECKED	JSS
ISSUE DATE	SEPTEMBER 2011
SHEET NO.	



05.06.22
PULTE – COMMUNITIES AT PLUM RUN
(Huggett Property)
Development Standards and Zoning Text
Grove City, Ohio

CURRENT ZONING: SF-1 (SINGLE FAMILY)

PROPOSED ZONING: PUD-R
(PLANNED UNIT DEVELOPMENT RESIDENTIAL)

Property Owners: S & W Huggett Ohio LLC
14337 US Rte. 23
Ashville, OH 43103

Applicant: Pulte Homes of Ohio LLC
475 Metro Place S. Ste. 200
Dublin, OH 43017

Authorized Representative: Thomas L. Hart
Painter and Associates
5029 Cemetery Road
Hilliard, OH 43026

I. PROPERTY

The property ("Property") consists of approximately 144.27 acres± acres north and west of London-Groveport Road (S.R. 665) and east of Jackson Pike (S.R. 104) as further described on the attached Final Development Plan, legal description (Exhibit A) and Survey (Exhibit B).

II. INTRODUCTION

The proposed community will consist of a mixture of single-family homes designed for families with children and free-standing patio/condominium homes designed with a minimum of two bedrooms on the first floor and no more than 50% of the first-floor area permitted on the second floor (if a second-floor option is chosen by the customer). The patio/condominium homes are designed for buyers seeking "first floor living" and typically appeal to the active adult consumer who desires community lifestyle services such as lawn/landscape maintenance and snow removal. Patio home lifestyle living is in high demand in the area as active adults continue to downsize but prefer to stay in their own community. The community is designed as an enclave opportunity for this type of living in an area with access to parks and trails in close proximity to children and grandchildren living nearby. The style, size and types of conventional single-family homes are consistent with the adjacent

communities, but include updated home designs, features and enhanced values.

The site plan will activate and allow regional access to the Plum Run stream corridor by providing scenic overlooks as well as by locating the regional multi-use path within the property and near the stream.

III. GENERAL PROVISIONS

- a. The provisions outlined within these development standards zoning text and the Subarea Map/Illustrative Plan(Exhibit C) shall apply to the 144.27 +/- acres of land as described in Exhibit A unless otherwise approved by Grove City Council. Other provisions of the Grove City Code (the "Code"), including the Standard drawings and other policies shall only apply to the extent that this zoning text does not address such matters. Any deviations from the standards outlined in the text may be granted by City Council, through the development plan.
- b. This PUD-R development is divided into three Subareas A, B, and C with applicable standards for each described herein.
- c. All provisions of this text are severable. If a court of competent jurisdiction determines that a word, phrase, clause, sentence, paragraph, subsection section or other provision is invalid or that the application of any part of the provision is invalid, the remaining provisions and the application of those provisions shall not be affected by that decision.
- d. Where there is or appears to be a conflict between the approved text and development plan, the more restrictive requirements shall apply. Where there is or appears to be a conflict between the text and the Code, the zoning text shall control.

IV. PERMITTED AND ACCESSORY USES

- a. The Communities at Plum Run PUD will be a residential neighborhood that shall contain detached single-family homes on public streets (Plum Run Ridge) and detached Patio/Condominium Homes (Plum Run Preserve) on private streets.
- b. A maximum number of detached single-family homes shall be permitted at three-hundred sixty (360) with lot standards and governed by regulations as further provided herein.
- c. Open spaces for the purpose of recreation, stormwater management and stream corridor protection zones, as estimated on plan exhibits and are to be confirmed with final engineering, surveying and construction plan review.

- d. Other permitted uses shall include entry features, site landscape fences or walls, signs, columns, related landscape lighting, multi-use paths and scenic overlooks to incorporate natural views, playground/tot lot, landscaping structures and benches to enhance open space, signage, trees and other plantings, protected natural areas of the stream corridor, model homes and related operations and other features incidental to detached single-family housing.
- e. Accessory uses shall be regulated in accordance with the Grove City Zoning Code.
- f. Model homes under City Code and with standards provided herein. Off- street parking for model homes may be permitted on one or more lots.
- g. Each home in Subareas A and B shall be on fee-simple platted lots. Homes in Subarea C are intended to be owned in a condominium form of ownership under ORC 5311.

V. GENERAL DEVELOPMENT STANDARDS

- a. Density. The density of the site shall not exceed Three Hundred Sixty (360) units, with a maximum gross density of +/-2.50 dwelling units per acre.
- b. Entryways. Landscaped entry features to the site will be located on London-Groveport Road (SR 665, two entrances for single family subareas) and Jackson Pike (SR 104) with lesser landscaping provided at Ravines End Drive and Ann Arundal Lane for the single-family Subareas A and B. . Separate entrances and entry features to the patio homes/condominium Subarea C from London-Groveport Road are also provided. The entrances shall incorporate design elements as depicted on exhibits and site plans and may include fencing, landscaping walls, signage, columns/piers, fountains, and related landscaping and lighting within open spaces. Entry signage is permitted at all entrances off Jackson Pike and London Groveport Road and shall meet signage requirements and setbacks of Chapter 1145 and the landscaping requirements of Section 1136.09(a)(1).
- c. Streets.
 - 1. All Public Streets shall be a minimum of 28 feet in width (as measured from face to face).
 - 2. All Private Streets shall be a minimum of 24 feet in width (as measured from face to face), owned and maintained by the Condominium or Homeowners Association. Private streets shall be permitted to deviate from the public roadway standards as part of the Final Development Plan for the patio/condominium subarea. Such deviations shall be approved as part of the

Final Development Plan.

3. The Developer shall work with the City staff to devise traffic calming measures and strategies to slow traffic on longer street runs, with special attention to Street A, from Jackson Pike and through Subarea A. Review of such traffic calming strategies shall be subject to the city's standards and may include the following: narrowing with mid-block curb "pinch points", especially at key pedestrian crossings, landscape street islands at key mid-street points, raised pavement at pedestrian or other street intersections, and striping techniques that create the driver perception of narrowing at the same pedestrian and street crossings.
- d. Sidewalks and Multi-Use Paths. Each street shall have a path and/or sidewalk on each side. An 8-foot-wide regional path shall be constructed and dedicated for public use to provide recreational opportunity to the residents of the neighborhood as well as the larger community and to access the natural areas bordering Plum Run as depicted on the Final Development Plan. Final sidewalk and path locations shall be approved on the Final Development Plan with allowance for the balancing of aesthetics, construction feasibility, maintaining grade, topography and drainage, and/or existing vegetation.
- e. Open Space. Open space is estimated on plan exhibits and is subject to final engineering, surveying and construction plan review.
 1. Open space is to be reserved for passive activities, as well as recreation, and will include benches and other seating areas, along with connecting paths and sidewalk accesses as generally shown on the Final Development Plan.
 2. Open space calculations may vary from the calculations provided on Final Development Plan Exhibits based on minor site plan adjustments for final engineering, utility and other field location decisions as shown on the final engineering plan/plats provided such final open space calculations meet the requirements of Section 1101.09(b) and such adjustments are approved by the City.
 3. Open space, including stormwater ponds, structures, facilities and paths shall be owned and maintained by the owners' associations, unless otherwise agreed with the City under an approved Development Agreement or if approved by Council at the time of platting.
 4. The Plum Run stream corridor and associated floodplain shall be preserved and may contribute to the required open space per Section 1101.09(b) provided that the area is activated by a path system and scenic overlooks.
- i. Open space amenities and specific open space acreages shall be depicted on the Final Development Plan as determined by final engineering. Open

space shall include Playgrounds and related facilities as depicted on plan exhibits and may also include elements such as bicycle racks and trash receptables for the convenience of homeowners and guests.

- f. **Site Lighting.** Site lighting on the public streets shall meet the current requirements of Grove City Code and the lighting fixtures will match the fixtures in the adjacent community of Scioto Meadows. The Private Street lighting will be similar to the fixtures in the Public Street area but will be owned and maintained by the owners' association (or via a "lease lighting" program entered into by the condominium association and the local utility provider, e.g., AEP). Street intersections shall be lighted with more limited lighting and spacing of lights on streets away from intersections.
- g. **Fencing.**
 - 1. Site landscape fencing ("off-lot") as depicted in plan exhibits, may be located at entry features and within perimeter setback areas along Jackson Pike and London Groveport Road and is to be white three-rail of a white vinyl, composite or weather resistant material.
 - 2. All "on-lot" fencing shall not exceed the following heights: unless otherwise specified: 48" for yard fences. 72" for privacy fences around patios, hot tubs, etc.
 - 3. In addition to the standards set forth in this text, all on-lot fence heights and styles are subject to written approval of the owners' association prior to installation.
 - 4. Pool fencing shall be as required by applicable governmental rules and regulations and owners' association documents.
 - 5. Yard fencing may be permitted within subareas A and B, **Single Family** homes under the following standards:
 - i. All fences must be located on a property owner's property line(s) or setback a minimum of twenty-four inches (24") from the property line. Placement of a fence on the property line constitutes the acknowledgement of the property owner that a fence on a neighboring property may be erected to "tie-in" to such fence so that duplicate, parallel fences on adjacent properties can be avoided.
 - ii. No fence may be erected within four feet (4') of an existing fence on an adjacent property except where such fences "come together" to form a connection point of such fences.
 - iii. If the erection of an approved fence would result in the creation of an area

on a property owner's lot that cannot be accessed for maintenance purposes other than from an adjacent owner's property, a gate must be erected in such fence so that the property owner can maintain his/her entire lot without trespassing/entering upon such neighbor's property.

- iv. No fence may be erected closer to any street than the platted building set-back line relative to such street. In the case of corner lots, the setbacks from BOTH streets shall apply.
 - v. Fences may not be erected to "clip a corner" or otherwise "box out" utility junction boxes that are located on the lot on which the fence is being erected. An Application that has been "Conditionally Approved" and which shows a fence alignment that results in such utility junction boxes being 'outside' of the fenced area of the yard are understood to require a change in alignment, such that the proposed fence follows property lines around the utility junction boxes, or runs parallel to property lines and is adequately set back from property lines to meet all of the foregoing requirements (including the requirement for one or more gates, if appropriate).
 - vi. All fences must be installed 'beauty-side out,' with all structural members (stringers) located on the side of the fence visible from the enclosed part(s) of the lot.
 - vii. Fences are required to comply with any and all height limitations established in City Code or community deed restrictions, whichever is more stringent.
 - viii. Fences must be erected along straight lines at consistent heights so as to provide a clean, professionally installed appearance; and all fence approvals are conditioned upon the duty of the property owner at all times to maintain the condition and appearance of the fence in good condition, including replacement of damaged, broken or missing fence boards, and painting/staining as appropriate from time-to-time (including gate hardware visible from the outside of the fenced yard). The 'standard' for fence maintenance and appearance is the general appearance of other fences and improvements within the same subdivision.
 - ix. Fences intended to enclose the rear yard of a Lot ("Rear-Yard Fencing") shall adhere to the style of fence as depicted on Exhibit F-1 attached hereto or substantially similar to style depicted in Exhibit F-1.
6. Yard fencing may be permitted within Subarea C **Patio Homes** under the following standards:
- i. Fences are required to comply with any and all height limitations

established in City Code or the applicable deed restrictions, whichever limitations are stringent.

- ii. Fences must be erected along straight lines at consistent heights so as to provide a clean, professionally installed appearance; and all fence approvals are conditioned upon the duty of the property owner at all times to maintain the condition and appearance of the fence in good condition, including replacement of damaged, broken or missing fence boards, and painting/staining as appropriate from time-to-time (including gate hardware visible from the outside of the fenced yard). The 'standard' for fence maintenance and appearance is the general appearance of other fences and improvements within the same condominium.
- 7. Patio privacy fencing may be permitted with subarea C Patio Homes under the following standards:
 - i. Privacy screening fences may not fully enclose a lot or patio. The privacy screening fence is only to be installed adjacent to patios and shall only be located along one side of any patio.
 - ii. Privacy screening is not to exceed 6' in height and should not extend longer than 20' beyond the depth of the structure.
 - iii. Unless otherwise permitted by the Design Review Board as established by the owners' association documents, the privacy screening is to be white vinyl with an open lattice style top as generally depicted on Exhibit "F-2".
- h. Retention Ponds. Retention Ponds shall comply and be constructed in accordance with Grove City's Stormwater Design Manual, unless otherwise permitted by this text.
- i. Landscaping, Screening, and Tree Preservation.
 - 1. Screening of Service Structures
 - a. Service structures shall be screened per Code (Section 1136.08).
 - 2. Unit Trees
 - a. There shall be three (3) trees planted per single-family residence.
 - b. Trees may be small, medium or large species and shall be a minimum of two (2) inches in caliper at installation or a minimum of six (6) feet in height, if evergreen.
 - c. Multi-stem and evergreen trees are permitted to account for trees required

for Subarea C.

- d. Trees shall be arranged within the front, side or rear yard areas with emphasis on the front facades in all Subareas. In addition, trees required for Subarea C may be located within any open space or setback area of any Subarea.
- e. In the case that trees die, trees shall be re-installed by the developer or the HOA per the final development plan.

3. Foundation Plantings

- a. A minimum of one-third (1/3) of the façade, or facades in the case of corner lots, fronting the public or private street shall be landscaped adjacent to the foundation with a minimum of five (5) shrubs, ground cover or ornamental plantings.
- b. The average height of foundation plantings at installation shall be twenty-four (24) inches minimum.

4. Perimeter Landscape Treatment

- a. A landscape treatment shall be provided in the open space reserve areas between residential lots and London-Groveport Road (SR 665) and Jackson Pike (SR 104) as detailed in the Final Development Plan, including the following:
 - i. Mounding shall vary in height and slope to create a rolling, natural appearance. Mound heights may range up to eight (8) feet, with average heights ranging from four (4) to six (6) feet. Slopes may range from 3:1 to 10:1. Mounding shall be located outside the public right-of-way and shall not obstruct site distance at any driveways or public intersections.
 - ii. Plantings at a rate of seven (7) evergreen trees, two (2) large deciduous trees and one (1) ornamental tree per one hundred (100) linear feet of lot perimeter.
 - iii. Evergreen trees shall be installed at a minimum height of six (6) feet. Deciduous trees shall be installed at a minimum caliper of two and one-half (2½) inches.
 - iv. Ornamental trees shall be installed at a minimum height of seven (7) feet, and shall be a minimum of 1.75" caliper at time of installation.

5. Street Trees

- a. Street trees shall be located along all streets within the Communities at Plum Run development and be spaced per chapter 1136.09(b) of City code. Street trees shall be owned and maintained by the Homeowners/Condominium Association, unless located on owner's lots. If trees die, street trees shall be replaced by the Homeowners/Condominium Association.
- b. Street trees shall vary in species to prevent a monoculture so long as they are in accordance with the City's planting list as approved by the City's Urban Forester. Invasive plant species - as listed by the Ohio Department of Natural Resources (ODNR) shall be prohibited and the use of native plants will be encouraged. The amount and type of trees shall be approved by the City's Urban Forester.
- c. At time of installation, all street trees shall have a clear canopy height of at least five feet (5') above the ground for traffic safety purposes.
- d. The minimum distance between the tree and the back of the street curb shall be two and one-half feet (2-1/2'). In the areas where a sidewalk exists or is proposed, the minimum distance between the tree trunk and both the edge of the street and the sidewalk shall be two feet.
- e. The minimum trunk caliper measured at six inches above the root ball for all street trees shall be no less than two (2) inches.

6. Retention Area Planting

- a. There shall be one (1) tree planted on site for every fifty (50) lineal feet of retention area perimeter. Required trees are not required to be evenly spaced around the perimeter and can be grouped within the reserve containing the retention area provided that design meets the overall design intent of planting requirements and appropriate character for the development.
- b. Retention areas may be planted to provide natural character in areas adjacent to the Plum Run stream corridor in order to maintain and enhance the native character.
- c. Jute matting is permitted as an option for shoreline protection.

7. Preservation of Trees and Wooded Areas

- a. A 'No Disturb Zone' shall be placed on lots over the twenty (20) feet adjacent to the existing Scioto Meadows subdivision. No building or

storage shall be placed and no removal of plantings of any kind shall be permitted, but the clearing of plant material that is dead, dying or posing a hazard or threat may be allowed as determined by the Urban Forester for The City of Grove City. Any portion of those areas designated as a tree preservation zone which do not contain trees or existing vegetation other than grass shall be maintained per the Grove City Property Maintenance Code. Alteration of grade is prohibited, except as approved by the City of Grove City, for utility placement, rear yard storm sewers or structures, path or street placement and in keeping with positive drainage practices and subdivision grading requirements.

- b. Existing healthy trees with a minimum of 4" diameter as measured at DBH within the 100-year floodplain or Stream Corridor Protection Zone of Plum Run shall be preserved with the exception of the need for utilities, pedestrian path, scenic overlooks, accesses and/or road crossings. Ash Trees shall be removed as directed by the City's Urban Forester.

8. Grass and Groundcover

- a. Any open space along a prominent corridor, such as Jackson Pike and London Groveport Road, shall be maintained as turf grass established by seed. Sod installations and irrigation systems shall be utilized at entries from Jackson Pike and London Groveport Road where such entries include added planting and landscape features as depicted on final development plans.
- b. Other areas of the Development not covered by landscaping shall be planted per Code (Section 1136.11).

j. Parking.

- 1. Four parking spaces shall be provided for each dwelling unit with a minimum of two spaces in an attached garage of each home and two spaces in each driveway.
- 2. On-Street parking will be restricted to one side of the street on public streets (Non-Fire Hydrant side of the street). "No Parking" signs shall be installed as directed by the fire department or public service. On-Street parking shall be prohibited on private streets within Subarea C that are less than 28 feet in width. Parking on one side of the street opposite hydrants shall be allowed in Subarea C where streets are wider than 28 feet.
- 3. The parking or storage of boats, trailers, or recreational vehicles in a driveway within the subdivision shall be prohibited.

k. Signage.

1. Project signage including temporary signage, model home signage, and marketing signage is permitted under this PUD and shall comply with City Code standards, unless otherwise defined/requested with Final Development Plans. Any additional signage not approved with the Final Development Plan proposed on site shall meet code requirements and shall be approved by sign permit.

l. Utilities. All new utilities shall be located underground except for pedestals for electricity, cable, phone, or similar utilities.

m. No trash dumpsters shall be used except during construction, alteration, or repair of a home. Each resident shall be responsible for trash pickup and have individual trash containers.

n. Mailboxes and locations shall meet standard postal service requirements.

1. CBUs shall be located in appropriate areas as depicted on site plans, and/or as determined by the USPS and City during the site construction process.

2. All mailboxes or CBUs shall have a uniform and consistent design. These fixtures shall be decorative in appearance and shall match the quality and theme of other site fixtures within the community.

3. Landscaping shall be installed around CBUs as permitted by the USPS.

o. Playgrounds are as depicted and located on site plan exhibits.

VI. LOT STANDARDS AND AREA REQUIREMENTS

a. Subarea Standards

Sub-Area	Min. Lot Width*	Ranch / One-Story	1-1/2 & Two-Story	Sample Home Types Anticipated for Each Subarea***
A	70'	2,200	2,400	Greenfield, Hilltop, Riverton, Westchester, Allison II
B	70'	1,600	2,200	Greenfield, Hilltop, Riverton, Westchester, Allison 11, Newberry, Linwood, Mercer, Continental, Prosperity, Mystique
C	52'	1,300		Trailblazer, Discover, Blue Rock, Passport

*Minimum lot widths shall be measured at the building line.

**A minimum of 7% of the lots in the single-family subareas shall accommodate side-

loaded garages.

***The sample home types are provided for illustration and are not the only models to be built. Other models, home elevations, and house plans are approvable subject to Section VIII of this text.

- b. The following standards shall apply to the Subareas A and B single family lots, known as Plum Run Ridge.

Min. Lot size.....	8,400 sf Sub. A and B
Max. building coverage	35%
Max. height	35'
Min. parking	4 spaces, including garages
Min. side yard setback	7.0'
Min. side yard setback adjacent R.O.W.	20'
Min. front yard setback	30' (Subarea A)
Min. front yard setback	25' (Subarea B)
Min. rear yard setback.....	20'

- c. The following standards shall apply to the Subarea C Patio/Condo Homes, known as Plum Run Preserve.

Setback - SR 665 (Existing R/W)	50' Building and Pavement
Setback (Perimeter)	25'
Max. building coverage	25%
Max. height	35'
Min. parking	4 spaces, including garages
Min. setback between units	10' total
Min. building setback from curb.....	6'
Min. building setback from sidewalk.....	4'
Min. rear yard areas	per plan details (+/-25')
Min. square footage	1,200 sf one and two story*

*Patio/condo homes shall include a minimum of two bedrooms on the first floor and no more than 50% of the first floor area shall be permitted on the second floor, where a second floor option is provided for.

VII. BUILDING MATERIALS AND ARCHITECTURE

The architectural character of the homes shall comply with the standards outlined in this text and provide the general character shown in the exhibits entitled ***Pulte Homes Architecture Portfolio prepared for the Communities at Plum Run*** submitted with this application and differentiated per subarea. Final building elevations shall be approved with building permits. Plans and/or elevations in addition to those submitted with this text, and after Final Development Plan approval may be also be approved with such approvals not to be unreasonably withheld, to allow for alterations based on changes in market demand and customer preferences and selections over time, so long as they are consistent with the quality, character

and proportions of the building elevations as submitted with this text and subject to the following standards being met:

- a. Permitted Materials. The exterior of the buildings shall be restricted to the following materials and architectural elements listed below. The primary materials and details used on front elevations of homes shall be carried through to and utilized on all other elevations of the home in a manner that creates continuity, cohesive design and balance among all facades. Primary exterior materials shall be:
 1. LP Smart Side and Trim or an equivalent siding product
 2. Fiber cement siding such as Hardie Plank TM
 3. Aluminum or vinyl soffits and fascia
 4. Stone, cultured stone
 5. Brick, brick veneer
 6. Single or double hung low-e vinyl windows
 7. Dimensional architectural shingles
 8. Vinyl siding premium/architectural grade with a minimum thickness of .044 mills
 9. Wood
- b. Masonry Requirements: Front – All front elevations are to include not less than 25% brick, brick veneer, stone or cultured stone, exclusive of windows, door openings and garage doors. Homes may be permitted without the requirement of 25% masonry on the front elevation provided they are compatible with or complementary to the built environment, include appropriate massing, are traditional in character and design and include a minimum of two architectural elements from the following list; window mullions, window trim wrap, bay window or bay elements, vertical board and batten or shake style siding elements (provided such elements are compatible with the design, style, and character of the home and subject elevation), shutters, or decorative louvers of at least 3 sq. ft.
- c. Trim Requirements: Sides and Rear Windows/Doors – 3 ½” actual minimum trim required, but not if window is bordered by masonry or includes shutters. Trim material for windows front, sides and rear maybe vinyl.
- d. Major roof elements shall have a minimum 6:12 pitch. Secondary or accent roofs may have 3:12 pitch. Roof materials shall be of a medium or dark color.
- e. Garage doors shall be paneled and of one color and material (windows shall be allowed if consistent with architectural character and theme).
- f. Overhangs and Eaves: Required 8” minimum from outside walls.
- g. Exterior Colors

1. Siding colors. Natural earth tones and/or warm neutral colors, including white. High-Chroma colors are not permitted
 2. Trim colors. Natural earth tones and/or warm neutral colors, including white. Complementary or contrasting siding color. High- Chroma colors are not permitted.
 3. Roof Colors. Shingle colors shall be from the color range of natural materials, such as, but not limited to wood shakes, slate, etc.
- h. Basements. All homes in Subarea A shall have partial or full basements, soil conditions permitting.
- i. Garages and driveways. All homes shall have an attached, minimum two-car garage. Garage door openings shall not exceed 45% of the width of the house façade for a two-car garage or 50% of the width of the house façade for a three-car garage, including the garage.
- j. All elevations of the homes shall be articulated in a manner as to represent a similar character on all facades.
- k. Diversity. The same home design with the same front elevation shall not be constructed on lots that are adjacent to or directly across the street from one another. A lot shall be deemed to be directly across the street from any other lot that is located in whole or in part between two imaginary straight-line extensions of the side lot lines for the first lot which extend to the opposite site of the public right-of-way on which the first lot has frontage, as illustrated on and subject to the conditions noted on the Attachment "A" ***Pulte Homes Façade Diversity Standard Exhibit***. On corner lots, the diversity requirement shall be applied to the street on which the home's front façade is located. Houses with the same footprint may be allowed within the distance and parameters described above provided that such houses incorporate substantial differences in the front elevations such as material changes, configuration of front porch, etc. The Development Department shall have the final approval as to whether a change is "substantial."
- l. Accessory Structures. No detached garages, sheds or other accessory structures shall be permitted.
- m. All exposed courses of foundations of all homes shall comply with chapter 1135.10 (E) of City Code.
- n. Deviations to these standards shall be approved by City Council with the Development Plan.

- o. Four-Sided Architecture – the following elements and details shall be considered “design elements” for creating the standards for four-sided architecture. All homes shall have at least one element on each elevation, no blank facades shall be permitted.
 - 1. Doors
 - 2. Porches
 - 3. A window or grouping of windows at least 6 sq. ft.
 - 4. Window mullions
 - 5. Window trim wrap
 - 6. Faux shutters
 - 7. Dormers (active and inactive)
 - 8. Bay window or bay elements
 - 9. Chimney
 - 10. Water table
 - 11. Decorative louvers of at least 3 sq. ft.
 - 12. Other design elements and materials used as accents, including but not limited to accent siding, band boards, brackets, corbels, and/or decorated A-frames; subject to approval of the Development Department.
- p. High Impact and Special Treatment Areas; (See plan exhibit of the same title.)
 - 1. “*High Impact Areas*” – High Impact Area lots are shown on plan exhibits. In such areas, where the front or side elevations of homes are exposed to the adjacent roadways a minimum of two of the design elements from the list under (n) shall be included on each such elevation.
 - 2. “*Special Treatment Areas*” – Mounding and/or landscape screening, consisting of 7 evergreen trees (minimum height of 6 feet at install), 2 deciduous trees (minimum 2 1/2" caliper at install) and 1 ornamental trees (minimum height of 7 feet at install) per 100 linear feet shall be installed in the open space areas adjacent to the sides and rears of homes backing to the Special Treatment Areas as depicted on the plan exhibits. Homes shall include four-sided architectural features as defined in (n).

VIII. PHASING

The property will be developed in phases as depicted on the Final Development Plan, subject to minor revisions necessitated by final engineering and design details.

IX. MODEL HOMES

- a. Model homes shall be permitted under City Code standards and regulations and the following additional standards shall apply:

1. Individual homes may be used as model homes by the Developer(s)/Builder(s) for the purpose of marketing and sale of new homes.
2. Manufactured and/or modular buildings are permitted for use as a sales office during the development of the project and the construction of residential units therein.
3. Model home parking may be established on lots adjacent to model homes for safety and convenience during the sales process.

X. HOMEOWNERS ASSOCIATION AND PATIO/CONDOMINIUM OWNERS ASSOCIATION

- a. Prior to occupancy by any residents in single-family subareas, the developer will establish a private, forced and funded homeowners' association. Control of the association shall be turned over to the residents according to Ohio Law. Association responsibility shall include care for the entryway, required tree installations and all open spaces after the development period and turnover date. All association responsibilities and obligations shall be set forth in the HOA declaration prepared and recorded by the developer prior to occupancy.
- b. Prior to the occupancy by any residents in the patio/condominium subarea the developer will establish a Patio/Condominium Owners' Association. (COA) Control of the association shall be turned over to the residents according to Ohio Law. The Patio/Condominium homeowners will be a member of a Condominium Association for maintenance of the open spaces, required tree installations and the entryway after the development period and turnover date. The Patio/Condominium Owners' Association responsibility shall include private street maintenance; snow plowing, lawn and landscape maintenance, street lighting and other duties as agreed to by members. All association responsibilities and obligations shall be set forth in the COA declaration prepared and recorded by the developer prior to occupancy.


SPECIAL TREATMENT AREAS



Black wrought iron or aluminum:



White vinyl with open lattice style top:




Approved Rear-Yard Fencing:


Black wrought iron or aluminum fence style shall adhere to the example below:




Condition 1
Front to Front
(Lot Offset $\leq 10'$)



Condition 2
Front to Front
(Lot Offset $> 10'$)



Condition 3
(Lot Separated by Street)



LEGEND:



Subject Facade

X Prohibited Same Home Design
with the Same Front Elevation
as Subject Facade

Model #100
Call 1-800-456-7890
www.pulte.com



PLUM RUN COMMUNITIES

GROVE CITY, OHIO



YOUR PLUM RUN RIDGE HOME, GREENFIELD

Greenfield
2,609+ Sq./Ft.
4 Bed, 2.5 Bath




YOUR PLUM RUN RIDGE HOME, GREENFIELD

Greenfield
2,609+ Sq./Ft.
4 Bed, 2.5 Bath



YOUR PLUM RUN RIDGE HOME, HILLTOP

Hilltop
2,889+ Sq./Ft.
4 Bed, 2.5 Bath



YOUR PLUM RUN RIDGE HOME, HILLTOP

Hilltop
2,889+ Sq./Ft.
4 Bed, 2.5 Bath





YOUR PLUM RUN RIDGE HOME, RIVERTON

Riverton
3,126+ Sq./Ft.
4 Bed, 2.5 Bath



YOUR PLUM RUN RIDGE HOME, RIVERTON


Riverton
3,126+ Sq./Ft.
4 Bed, 2.5 Bath



YOUR PLUM RUN RIDGE HOME, WESTCHESTER


Westchester

3,300+ Sq./Ft.
4 Bed, 2.5 Bath



YOUR PLUM RUN RIDGE HOME, WESTCHESTER

Westchester
3,300+ Sq./Ft.
4 Bed, 2.5 Bath





YOUR PLUM RUN RIDGE HOME, ALLISON

Allison
3,337+ Sq./Ft.
4 Bed, 2.5 Bath



YOUR PLUM RUN RIDGE HOME, ALLISON

Allison
3,337+ Sq./Ft.
4 Bed, 2.5 Bath



YOUR PLUM RUN RIDGE HOME, NEWBERRY

Newberry
2,376+ Sq./Ft.
4 Bed, 2.5 Bath



YOUR PLUM RUN RIDGE HOME, NEWBERRY

Newberry
2,376+ Sq./Ft.
4 Bed, 2.5 Bath



First Floor



Second Floor



YOUR PLUM RUN RIDGE HOME, LINWOOD

Linwood
2,456+ Sq./Ft.
4 Bed, 2.5 Bath



YOUR PLUM RIDGE RUN HOME, LINWOOD

Linwood
2,456+ Sq./Ft.
4 Bed, 2.5 Bath



YOUR PLUM RUN RIDGE HOME, MERCER

Mercer
2,605+ Sq./Ft.
4 Bed, 2.5 Bath



YOUR PLUM RUN RIDGE HOME, MERCER

Mercer
2,605+ Sq./Ft.
4 Bed, 2.5 Bath



First Floor



Second Floor

YOUR PLUM RUN RIDGE HOME, CONTINENTAL

Continental
2,873+ Sq./Ft.
4 Bed, 2.5 Bath



YOUR PLUM RUN RIDGE HOME, CONTINENTAL

Continental
2,873+ Sq./Ft.
4 Bed, 2.5 Bath



First Floor



Second Floor


YOUR PLUM RUN RIDGE HOME, PROSPERITY

Prosperity
1,646+ Sq./Ft.
2 Bed, 2 Bath




YOUR PLUM RUN RIDGE HOME, PROSPERITY

Prosperity
1,646+ Sq./Ft.
2 Bed, 2 Bath




YOUR PLUM RUN RIDGE HOME, MYSTIQUE

Mystique
1,841+ Sq./Ft.
2 Bed, 2 Bath



YOUR PLUM RUN RIDGE HOME, MYSTIQUE

Mystique
1,841+ Sq./Ft.
2 Bed, 2 Bath




YOUR PLUM RUN PRESERVE HOME, DISCOVER

Discover
1,386+ Sq./Ft.
2 Bed, 2 Bath




YOUR PLUM RUN PRESERVE HOME, DISCOVER

Discover
1,386+ Sq./Ft.
2 Bed, 2 Bath




Floor plans




YOUR PLUM RUN PRESERVE HOME, BLUE ROCK

Blue Rock
1,489+ Sq./Ft.
2 Bed, 2 Bath




YOUR PLUM RUN PRESERVE HOME, BLUE ROCK

Blue Rock
1,489+ Sq./Ft.
2 Bed, 2 Bath




YOUR PLUM RUN PRESERVE HOME, PASSPORT

Passport
1,503+ Sq./Ft.
2 Bed, 2 Bath



YOUR PLUM RUN PRESERVE HOME, PASSPORT

Passport
1,503+ Sq./Ft.
2 Bed, 2 Bath



YOUR PLUM RUN PRESERVE HOME, TRAILBLAZER

Trailblazer
1,222+ Sq./Ft.
2 Bed, 2 Bath



Date: 08/03/22
Introduced By: Mr. Schottke
Committee: Lands
Originated By: Plan. Comm.
Sponsor: _____
Emergency: 30 Days
Current Expense: _____

No.: CR-49-22
1st Reading: 08/15/22
Public Notice: _____
2nd Reading: _____
Passed: _____ Rejected: _____
Codified: _____ Code No: _____
Passage Publication: _____

*Postponed
to 10/13
12-119*

RESOLUTION NO. CR-49-22

A RESOLUTION TO APPROVE THE DEVELOPMENT PLAN FOR BEULAH PARK, SUBAREA C PERMITTING LENNAR HOMES VENTURE COLLECTIONS

WHEREAS, on August 02, 2022, the Planning Commission recommended approval of the Development Plan for Beulah Park, Subarea C, to permit the Lennar Homes Venture Collections in this area, as submitted.

NOW, THEREFORE BE IT RESOLVED BY THE COUNCIL OF THE CITY OF GROVE CITY, STATE OF OHIO, THAT:

SECTION 1. This Council hereby approves the Development Plan for Beulah Park, Subarea C, to permit the Lennar Homes Venture Collections in this area, as submitted.

SECTION 2. This approval shall be good for 12 months from the date passed, or as otherwise provided in Section 1101.07(b) of the Codified Ordinances of the City of Grove City, Ohio.

SECTION 3. This resolution shall take effect at the earliest opportunity allowed by law.

Ted A. Berry, President of Council

Richard L. Stage, Mayor

Passed:
Effective:

Attest:

Tami K. Kelly, MMC, Clerk of Council

I Certify that this resolution
is correct as to form.

Stephen J. Smith, Director of Law

Date: 09/12/22
Introduced By: Mr. Schottke
Committee: Lands
Originated By: Plan. Comm.
Approved: _____
Emergency: 30 Days: _____
Current Expense: _____

No.: CR-56-22
1st Reading: 09/19/22
Public Notice: _____
2nd Reading: Postponement requested
Passed: _____ Rejected: to 11-07-22
Codified: _____ Code No: 12-05-22
Passage Publication: 12-19-22

RESOLUTION NO. CR-56-22

A RESOLUTION TO APPROVE THE DEVELOPMENT PLAN FOR COMMUNITIES AT PLUM RUN LOCATED NORTH OF S.R. 665 AND EAST OF S.R. 104

WHEREAS, on September 06, 2022, the Planning Commission recommended approval of the Development Plan for Communities at Plum Run with the following stipulation:

1. Mounding, 3 to 4 feet in height, shall be installed along the east property line of Subarea C, where adjacent to 790 London-Groveport Road. The mounding shall include one row of evergreen trees planted along the top and one row between the mounding and the property line.

NOW, THEREFORE BE IT RESOLVED BY THE COUNCIL OF THE CITY OF GROVE CITY, STATE OF OHIO, THAT:

SECTION 1. This Council hereby approves the Development Plan for Communities at Plum Run located North of S.R. 665 and East of S.R. 104, contingent upon the stipulation set by Planning Commission.

SECTION 2. This approval shall be good for 12 months from the date passed, or as otherwise provided in Section 1101.07(b) of the Codified Ordinances of the City of Grove City, Ohio.

SECTION 3. This resolution shall take effect at the earliest opportunity allowed by law.

Ted A. Berry, President of Council

Richard L. Stage, Mayor

Passed:

Effective:

Attest:

Tami K. Kelly, MMC, Clerk of Council

I Certify that this resolution
is correct as to form.

Stephen J. Smith, Director of Law

Date: 12/13/22
Introduced By: Mr. Schottke
Committee: Lands
Originated By: Plan. Comm.
Sponsor: _____
Emergency: 30 Days: _____
Current Expense: _____

No.: CR-68-22
1st Reading: 12/19/22
Public Notice: _____
2nd Reading: _____
Passed: _____ Rejected: _____
Codified: _____ Code No: _____
Passage Publication: _____

RESOLUTION NO. CR-68-22

A RESOLUTION TO APPROVE THE PRELIMINARY DEVELOPMENT PLAN FOR THE HARRIS PROPERTY LOCATED NORTH OF S.R. 665 AND WEST OF BORROR ROAD

WHEREAS, on December 06, 2022, the Planning Commission recommended approval of the preliminary development plan for the Harris Property located North of State Route 665 and West of Borrор Road, with the following stipulation:

1. The Applicant shall work with Staff to determine appropriate screening standards between the proposed development and existing homes and where lost back to public rights-of-way.

NOW, THEREFORE BE IT RESOLVED BY THE COUNCIL OF THE CITY OF GROVE CITY, STATE OF OHIO, THAT:

SECTION 1. This Council hereby approves the Preliminary Development Plan for the Harris Property located North of State Route 665 and West of Borrор Road, contingent upon the stipulation set by Planning Commission.

SECTION 2. This resolution shall take effect at the earliest opportunity allowed by law.

Ted A. Berry, President of Council

Richard L. Stage, Mayor

Passed:
Effective:

Attest:

Tami K. Kelly, MMC, Clerk of Council

I Certify that this resolution
is correct as to form.

Stephen J. Smith, Director of Law

No.:	C-74-22
1st Reading:	12/06/22
Public Notice:	12/07/22
2nd Reading:	12/19/22
Passed: _____	Rejected: _____
Codified: _____	Code No: _____
Passage Publication:	

AN ORDINANCE TO APPROPRIATE \$1,900,000.00 FROM THE DEPOSIT TRUST FUND AND REDUCE APPROPRIATION AMOUNTS FOR VARIOUS FUNDS

I Certify that there is money in the treasury, or is in the process of collection, to pay the within

Date: 12/12/22
Introduced By: Mr. Holt
Committee: Finance
Originated By: Mayor Stage
Approved: _____
Emergency: 30 Days: _____
Current Expense: XX

No.: C-75-22
1st Reading: _____
Public Notice: 12-06-22
2nd Reading: 12-19-22
Passed: _____ Rejected: _____
Codified: _____ Code No: _____
Passage Publication: _____

ORDINANCE C-75-22

AN ORDINANCE TO MAKE APPROPRIATIONS FOR CURRENT EXPENSES AND OTHER EXPENDITURES FOR WHICH THE CITY OF GROVE CITY MUST PROVIDE DURING THE TWELVE MONTHS ENDING DECEMBER 31, 2023

WHEREAS, appropriations are required effective January 1, 2023 to provide for the current expenses and other expenditures associated with the operations of the City for the fiscal year ending December 31, 2023.

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF GROVE CITY, STATE OF OHIO, THAT:

SECTION 1. The following appropriations are hereby made in the General Fund (100):

Department	#	Personal Services	All Other	2023 Budget Request
CITY COUNCIL	100010	364,158	42,260	406,418
ADMINISTRATION	100030	608,616	78,597	687,213
FINANCE	100040	492,264	846,610	1,338,874
LAW	100050	0	691,000	691,000
POLICE	100070	11,144,916	1,648,620	12,793,536
COMMUNICATIONS	100071	2,059,941	118,200	2,178,141
MAYOR'S COURT	100072	322,141	192,943	515,084
BUILDING	100080	1,359,556	323,349	1,682,905
LANDS & BUILDINGS	100090	2,559,903	4,149,830	6,709,733
PARKS & REC.	100100	1,075,976	721,250	1,797,226
FLEET MAINTENANCE	100110	274,778	170,660	445,438
GENERAL GOV.	100120	651,163	16,437,000	17,088,163
HEALTH	100160	0	535,000	535,000
INFORMATION TECH	100250	1,245,926	2,191,290	3,437,216
COMMUNITY RELS	100260	207,135	170,500	377,635
HUMAN RESOURCE	100270	116,360	115,500	231,860
DEVELOPMENT	100310	790,193	560,700	1,350,893
GENERAL FUND		23,273,026	28,993,309	52,266,335

SECTION 2. The following appropriations are hereby made in the following funds:

Department	#	Personal Services	All Other	2023 Budget Request
STREET	101400	1,815,695	628,165	2,443,860
STATE HIGHWAY	102000	0	205,000	205,000
POLICE PENSION	103000	1,665,511	25,000	1,690,511
GENERAL RECREATION	104000	965,652	532,500	1,498,152
CITY PERMISSIVE MVL	105000	0	380,000	380,000
COUNTY PERMISSIVE MVL	106000	0	130,000	130,000
SENIOR NUTRITION	108000	0	25,000	25,000
DRUG LAW ENF	109000	0	95,340	95,340
COMMUNITY DEV.	112600	175,749	572,650	748,399
COMM. ENVIRONMENT	113000	0	136,700	136,700
LAW ENFORCE. ASSIST	114000	0	14,475	14,475
ENFORCEMENT & ED	115000	0	10,000	10,000
COURT COMPUTER	120000	0	38,175	38,175
BIG SPLASH	125700	0	315,375	315,375
BOND RETIREMENT	201000	0	2,487,300	2,487,300
BUCKEYE TIF	202000	0	3,359,190	3,359,190
PINNACLE TIF	203000	0	9,304,655	9,304,655
ROCKFORD TIF	136000	0	223,200	223,200
SR665 TIF	204000	0	858,320	858,320
LUMBERYARD TIF	205000	0	338,665	338,665
BEULAH PARK TIF	206000	0	364,930	364,930
CAPITAL IMPROVEMENTS	305000	0	19,257,895	19,257,895
RECREATION DEVELOP.	306000	0	488,000	488,000
WORKERS COMP.	401000	0	275,000	275,000
WATER	501000	0	1,029,340	1,029,340
SEWER	502800	593,777	1,054,235	1,648,012
DEPOSIT TRUST	601000	0	3,000,000	3,000,000
CONVENTION BUREAU	609000	0	660,000	660,000
SCIOTO TOWNSHIP JEDD	620000	0	1,400,000	1,400,000
TOTALS		5,216,384	47,209,110	52,425,494

SECTION 3. The Director of Finance is hereby authorized to issue his check against the appropriate city account for the amount appropriated and for the purpose stated in this ordinance upon receiving the proper certificate and vouchers therefore approved by an officer authorized by law to approve same or authorized by an ordinance of Council to make expenditures.

SECTION 4. The salary for the Administrative Assistant shall be determined by the Mayor within the range of \$147,000 - \$187,000 and shall be \$182,000 for the period January 1, 2023 to December 31, 2023, and the salary for the Clerk of Council shall be \$100,459 for the period January 1, 2023 to December 31, 2023. They shall receive the same benefits outlined in Chapter 161 of the Codified Ordinances.

SECTION 5. The Convention Bureau appropriation of \$660,000 shall be distributed as shown:

Grove City Area Convention and Visitors Bureau	\$475,000
Grove City Chamber of Commerce	\$85,000
Grove City Town Center Inc.	\$90,000
Little Theater Off Broadway	\$10,000

SECTION 6. This ordinance shall go into effect at the earliest opportunity allowed by law, with appropriation amounts being effective January 1, 2023.

Ted A. Berry, President of Council

Passed:
Effective

Richard L. Stage, Mayor

Attest:

Tami K. Kelly, MMC, Clerk of Council

I Certify that this ordinance is correct as to form.

Stephen J. Smith, Director of Law

I certify that there is money in the treasury, or is in the process of collection, to pay the within ordinance.

Michael A. Turner, Director of Finance